



MEMORANDUM

TO: HOLDERS OF PLANS AND SPECIFICATIONS
FROM: DIVISION OF SOIL CONSERVATION & SNYDER & ASSOCIATES
DATE: November 26, 2013
SUBJECT: HARRINGTON AML (IA-235)
ADDENDUM No. 1

Enclosed is one copy of Addendum No. 1 for the above referenced project. Acknowledge receipt of this addendum on the Proposal Form prior to submission.

Also please acknowledge receipt of this addendum by signing below and faxing or emailing a scan of this page back to 515-965-1629 or wfarrand@snyder-associates.com as soon as possible.

I acknowledge receipt of Addenda #_____.

Company Name (Please Print) _____

Name (Please Print) _____

Authorized signature _____ Date _____

Title _____ Phone _____

**ADDENDUM No. 1
TO THE PLANS AND SPECIFICATIONS FOR
HARRINGTON AML RECLAMATION PROJECT (IA-235)**

The information contained in this addendum modifies, supplements, or replaces information contained in the contract documents and on the drawings, and is hereby made a part of the contract documents.

I. SCOPE

This Addendum No. 1 consists of pages 1 through 3 with attachments including general clarifications as listed under Part II, revisions to the front end bidding documents as listed under Part III, and revisions to the Construction Drawings as listed under Part IV. The primary modification to the bidding documents reflects the revision of the bid letting date from December 2, 2013 to December 3, 2013.

Enclosed with this Addendum is a revised Proposal (Document C) that includes the revisions listed below for use when submitting bids.

II. GENERAL CLARIFICATIONS

- A. Materials and debris salvaged to the property owner is considered incidental to the "Site Clearing and Preparation" bid item and will not be paid for separately. Waste debris found onsite and removed to an off-site waste disposal area will be paid for based on the "Off-site Waste Disposal" bid item.
- B. Contractor is required to obtain permission for burning of landscape waste from any residence within ¼ mile of the burn location. For bidding purposes, bidder should assume that these waivers will be granted from the property owners.
- C. Bid item for "Terraces" includes only the excavated terraces constructed according to Detail 2, Sheet 16 and noted as "Terrace" on the Construction Drawings. Features noted as "Bench Terrace" or "Diversion Berm" will not be measured separately for payment but is considered incidental to the bid item for "Excavation".
- D. Furnishing and placing filter fabric under rip rap is considered incidental to the bid item for "Riprap".
- E. Bid item for "Tile, 8" Outlet" includes furnishing and installing the 20-foot section of solid wall PVC as well as the other specified components. Measurement of tiling to be paid on a lineal foot basis will not include this section of the pipe.

- F. Fence channel crossings constructed according to Detail 2, Sheet 17 on the Construction Drawings are considered incidental to the “Field Fence” bid item and will be measured for payment along with the typical field fence construction.

III. BIDDING DOCUMENTS

- A. *Document A – Notice to Bidders*, page A-1, replace the first sentence with the following:
 “Sealed bids will be received by the Iowa Department of Agriculture and Land Stewardship, Division of Soil Conservation, 502 East 9th Street, Des Moines, Iowa, 50319, until **3:00 p.m.** local time, on the **3rd day of December, 2013** and opened at a public meeting and read aloud on the date last mentioned.”
- B. *Document C – Proposal and Schedule of Prices*, page C-1, replace the Time and Date of Bid Opening with the following:
“3:00 p.m., December 3, 2013
 Conference Room 2
 IDALS-DSC
 502 East 9th Street
 Des Moines, Iowa 50319”

IV. CONSTRUCTION DRAWINGS

- A. *Sheet 2 of 21 – Project Notes, Legend & Quantities*, correct Sheet No. references by replacing “Tile Riser Schedule” with the following table:

TILE RISER SCHEDULE								
RISER I.D.	SHEET No.	DIAMETER (in)	INTAKE MATERIAL	HOLES QTY/FT	HOLE SIZE (in)	LOW PT. ELEV.	RISER HEIGHT (ft)	BAR GUARD
						(ft)		(Y/N)
R-1	10	8	Plastic	56	1	687.5	2.0	Y
R-2	11	8	Plastic	56	1	724	2.0	N
R-3	11	8	Plastic	56	1	724	2.0	N
R-4	11	8	Plastic	56	1	723	2.0	N

NOTES:

1. Risers without bar guard to have closed top.

- B. *Sheet 2 of 21 – Project Notes, Legend & Quantities*, correct Sheet No. references by replacing “Tile Schedule” with the following table:

TILE SCHEDULE								
PIPE I.D.	SHEET No.	DIAMETER (in)	PIPE MATERIAL	LENGTH (ft)	MIN. SLOPE (%)	INV. ELEV. UP (ft)	INV. ELEV. DOWN (ft)	OUTLET (Y/N)
P-1	10	8	Non-perforated Plastic	90	10.0	684.0	670.0	Y
P-2	11	8	Perforated Plastic	235	0.5	720.5	719.3	N
P-3	11	8	Perforated Plastic	140	0.5	719.3	718.6	N
P-4	11	8	Non-perforated Plastic	115	15.0	718.6	697.0	Y

NOTES:

1. Invert elevations are approximate based on minimum slope and rough grade elevations. Field adjustments may be necessary to accommodate final grades.
2. Lengths shown do not include outlet/end treatment where applicable. Outlet/end treatment is a separate bid item.

END OF ADDENDUM No. 1

SCHEDULE OF PRICES

Name of Bidder:

Harrington AML Reclamation Project
 Sections 5 and 8, Township 70 North, Range 13 West
 Davis County, Iowa

Bid No. IA-235

Item Amount No.	Work or Material	Spec No.	Estimated Quantity	Unit	Unit Price	Total
1	Mobilization	02100	1	LS		
2	Site Clearing and Preparation	02100	8.0	AC		
3	Off-site Waste Disposal	02100	15	TON		
4	Surface Roughening	02120	3.0	AC		
5	Erosion Control Mulching @ 2 ton/ac	02120	4.0	AC		
6	Silt Fence - Installation	02120	7,100	LF		
7	Silt Fence - Removal	02120	7,100	LF		
8	Check Dams	02120	15	TON		
9	Stabilized Construction Entrance - Installation	02120	35	TON		
10	Stabilized Construction Entrance - Removal	02120	1	EA		
11	Excavation	02200	46,000	CY		
12	Excavation - Select Borrow	02200	2,000	CY		
13	Riprap	02300	1,130	TON		
14	Erosion Stone	02300	85	TON		
15	Erosion Control Mat, Type 2.D	02300	500	SY		
16	Riser, 8"	02300	4	EA		
17	Tile, 8" Perforated	02300	375	LF		
18	Tile, 8" Non-perforated	02300	205	LF		
19	Tile, 8" Outlet	02300	2	EA		
20	Terraces	02300	610	LF		
21	Agricultural Lime, Subgrade @ 20 ton ECCE/ac	02400	160	TON		
22	Mulch, Subgrade @ 5 ton/ac	02400	8.0	AC		
23	Field Fence	02500	1,150	LF		
24	Single Gate, 12' Wide	02500	2	EA		
25	Agricultural Lime, Seeding @ 5 ton ECCE/ac	02700	40	TON		
26	Fertilizer, Nitrogen (N) @ 100 lb/ac	02700	800	LB		
27	Fertilizer, Phosphorous (P) @ 50 lb/ac	02700	400	LB		

Item Amount No.	Work or Material	Spec No.	Estimated Quantity	Unit	Unit Price	Total
28	Fertilizer, Potassium (K) @ 100 lb/ac	02700	800	LB		
29	Interim Seeding	02700	8.0	AC		
30	Mulch, Seeding @ 2 ton/ac	02700	8.0	AC		

TOTAL BASE BID \$ _____

END OF DOCUMENT C